

## 13. 2 MCC Buildings

- Motor Controls for all drivers on each site are housed in these building.
- Both MCC buildings include instrumentation termination cabinets.
- Both the sites are equipped with programmable logic controllers (PLC) and Human Machine Interfaces (HMI's) and small control rooms.
- The Production site MCC also includes the control equipment for the microseismic monitor and a server rack.

