

Document Title: Keystone XL Pipeline-Grassy Creek Pump Station MV
 Metering Cabinet Three Line Diagram

Document Number: 25472-101-V2A-EMM0-W0006

Revision Number: 1

PO Number: 4500249594

Material Requisition Number: 08, BI

Applicable Tag#: 128-GRSSY-B0-JIT-01



Shermco Industries
 1033 Kearns Cres.
 Regina, SK
 Canada, S4K 0A2
 (306) 949-8131

CODE 1: Work may proceed.




Permission to proceed does not constitute acceptance or approval of design details, calculations, analyses, test methods or materials developed or selected by the supplier and does not relieve the supplier from full compliance with contractual obligations.

Name: fiona_jiang

Date: 07/07/2020

Supplier Rev.	Rev Date DD-MMM-YYYY	Reason for Issue	Supplier Name
0	15-Jun-2020	First Issue with Referbishment Update	Shermco Industries
1	30-Jun-2020	Fixed Cover Page	Shermco Industries



NOTES:

1. INTERLOCK KEY SCHEME:

INITIAL CONDITION:

HVCB IS CLOSED WITH KEY "A" CAPTIVE IN ITS RESPECTIVE KEY INTERLOCK. METERING CABINET COMPARTMENTS ARE LOCKED CLOSED WITH NO KEYS PRESENT IN THEIR RESPECTIVE KEY INTERLOCKS. THE 5-KEY TRANSFER INTERLOCK HAS FOUR "B" KEYS CAPTIVE IN ITS SECONDARY CYLINDER POSITIONS.

TO HAVE ACCESS TO METERING CABINET COMPARTMENTS:

1. OPEN HVCB
2. TURN KEY "A" ON LO INTERLOCK ON HVCB TO LOCK OPEN. KEY "A" IS NOW FREE.
3. INSERT KEY "A" IN THE 5-KEY TRANSFER INTERLOCK AND TURN. KEYS "B" ARE NOW FREE.
4. USE THE "B" KEYS TO UNLOCK THE METERING COMPARTMENTS DOORS.

REVERSE SEQUENCE TO RESTORE SERVICE.

Association of Professional Engineers & Geoscientists
of Saskatchewan
CERTIFICATE OF AUTHORIZATION
Shermco Industries Canada Inc. dba Magna Electric Corporation
Number 29927
Permission to Consult held by:
Discipline Sk. Reg. No. Signature
ELECTRICAL 35017 *[Signature]*

**ISSUED FOR
CONSTRUCTION**

NO.	DRAWING REFERENCES	REV	REVISION DESCRIPTION	DRAWN	DATE	CHKD	APPD	CLIENT
		B	ISSUED FOR CONSTRUCTION	DL	04/02/2013	ID		
		1	FIELD CHANGES	HW	29/06/2020	BT	SM	

PROFESSIONAL ENGINEER
SASKATCHEWAN
S.K. MAHIN
MEMBER 35017
2-06-3-
VIA MAIL ONLY

NOTICE
This document contains information that is the property of Magna Electric Corporation (MEC). All original drawings, documents and reports are issued in confidence that the client will not use or permit the use of the information contained therein to be copied, reproduced or disclosed to others without the written consent of MEC. MEC accepts no liability for unauthorized use.

Si
Shermco Industries
One Line. One Company.

BY	DESIGNED	
EJP	ID	
DATE 11/06/2012	11/06/2012	
CHECKED	APPROVED	CLIENT APPD.
ID		
11/06/2012		
SCALE	NTS	
PROJECT NO.	20-T262R-1082	

CLIENT	TCPL
TITLE	KEystone XL PIPELINE-GRASSY CREEK PUMP STATION MV METERING CABINET THREE LINE DIAGRAM
DWG. NO.	T262R-050-001-02

REV
▲